

## **ADDENDUM NO. 2**

for  
**TOILET RENOVATIONS AT PITMAN ELEMENTARY SCHOOL**  
located at 138 E Holly Ave, Pitman, NJ 08071

for the  
**PITMAN SCHOOL DISTRICT**  
Pitman, Gloucester County, New Jersey

**Issued: December 1, 2025**

**FVHD PROJECT #5525-4**

**FRAYTAK VEISZ HOPKINS DUTHIE, P.C.**  
**Architects – Planners**  
1515 Lower Ferry Road ,Trenton, NJ 08618  
Tel: 609.883.7101 - Fax: 609.883.2694  
William D. Hopkins III, AIA, LEED AP  
No. 21AI01706000

**GILLAN & HARTMANN, INC.**  
**Consulting MEP Engineers**  
140 Whitaker Avenue, Suite 300  
Mont Clare, PA 19453  
M. Steven Gillan, P.E.  
No. 24GE4470000

### **INTENT**

**This Document supersedes all conflicting and contrary information in said Bid Documents. Said documents are hereby amended in certain particulars as described herein after. Unless specifically noted or specified hereinafter all work shall conform to the applicable provisions of the Bid Documents. Bidders shall acknowledge receiving this document and previously issued Addenda No. 1 on the Bid Proposal Form.**

This Addendum includes two pages.

## **CLARIFICATION**

New electrical work shall include furnishing and installing electric power for the following number of Xlerator XL-W electric hand dryers in the following toilet rooms:

Two (2) in Boys Toilet Room 101  
Three (3) in Girls Toilet Room 104  
Two (2) in Boys Toilet Room 201  
Two (2) in Girls Toilet Room 204  
Two (2) in Boys Toilet Room 301  
Two (2) in Girls Toilet Room 304  
One (1) in Staff Toilet Room 305  
One (1) in Staff Toilet Room 306

## **REQUEST FOR INFORMATION (RFI'S)**

1. Question: Stated existing zoned FACP is analog in nature and will not integrate with addressable devices. Addressable devices are noted on the print. Is there a requirement to change the control to be addressable?

Response: The Toilet Room Renovation project 5525-4 requires the replacement of existing Zoned/Conventional fire alarm devices wired from existing Zoned/Conventional fire alarm circuits. On this project, we are replacing old zoned/conventional devices with new zoned/conventional devices one for one. This work should not affect the work being done on the HVAC renovation project where we are replacing the existing main fire alarm control panel.

**END OF ADDENDUM NO. 2**